

Associated Engineering (Sask.) Ltd.

203 - Five Donald Street Winnipeg, MB R3L 2T4 Canada www.ae.ca

TEL: 204.942.6391

May 23, 2023 File: 2019-4231

Robert Boswick, P. Eng. Senior Environmental Engineer Environmental Approvals Branch Manitoba Conservation and Climate 1007 Century Street Winnipeg MB R3H 0W4 Canada

Re: LICENCE 1666 S3

ST. CLAUDE LAGOON - NOTICE OF ALTERATION Rev2.

Dear Mr. Boswick:

In accordance with the Environment Act (Section 14), this submission is a request for minor alterations to said facility operating under Licence Number 1666 S3 for the RM of Grey.

#### 1 PROJECT DESCRIPTION

#### 1.1 LAGOON AERATION REPLACEMENT

The existing aeration system is past its useful life and numerous leaks and repairs reduces its efficiency. It is currently proposed to replace the system in 2023/24. Prior to replacement, the accumulated biosolids in all three cells will be removed for land disposal (EAP under separate submission). Once the biosolids are removed, the new aeration piping and diffusers will be replaced in the cells.

The new aeration system is to be designed for the projected 2042 organic load of 355 kg BOD/day with an average day flow of  $396 \text{ m}^3/\text{day}$ . It is proposed to design the new aeration system to match the exiting treatment rate of 355 kg BOD/day and to maintain at least 2.0 mg/L of dissolved oxygen in the water column.

The following Table summarizes the current and future loadings to the facility.


	2023 UPDATED	2042 UPDATED
Contributing Population	600 Residents	700 Residents
ORGANIC LOADING		
Typical BOD Load per Resident	0.077 kg/BOD/person/day	0.077 kg/BOD/person/day
Total Daily BOD Load from Residents	46 kg BOD/day	54 kg BOD/day
Total Daily BOD Load from Abattoir	3 kg BOD/day	3 kg BOD/day






	2023 UPDATED	2042 UPDATED
Total Daily BOD Load From Dairy	270 kg BOD/day (BOD - 2,000 mg/L)	270 kg BOD/day (BOD - 2,000 mg/L)
TOTAL ORGANIC LOADING TO LAGOON:	319 kg BOD/day	327 kg BOD/day
APPROXIMATE DESIGN CAPACITY : (winter, if functional)	355 kg BOD/day	355 kg BOD/day
Hydraulic Loading		
Per capita wastewater contribution (includes normal infiltration amount)	373 Litres /capita /day	373 Litres /capita /day
Average daily flow from Residents	224 m <sup>3</sup> /day	261 m³/day
Dairy Industry wastewater contribution	135 m³/day	135 m³/day
Climate Adaptation (wetter springs - extreme infiltration)	120	30,000 m³
TOTAL HYDRAULIC LOAD TO LAGOON:	81,493 m <sup>3</sup> (over 227 days)	119,892 m³ (over 227 days)
AVAILABLE STORAGE (to FSL):	81,000 m <sup>3</sup>	119,000 m³ (raised berms)
HYDRAULIC LAGOON CAPACITY USED:	100%	100.7%


The following Figure shows the propose new aeration layout in the cells.







The new aeration system will be a partially buried header in the common berm. This design improves access to berms for grass cutting and maintenance. The laterals and diffusers will also be submerged to the cell floor, unlike suspended laterals that would move with water levels.



The new aeration system will also include a new blower building on the existing berms with new aeration blowers. The old blower building would be demolished with the old aeration system once the new system is operational.

The old aeration system (from the 1980's) is prone to failure and short circuiting when leaks occur. As a result, the system can be challenged to adequately treat the incoming wastewater.

For robustness, the design target of the new aeration is to maintain the existing loading rate of 355 kg BOD/day, even as the estimated loading is projected to be lower. This provides some added capacity to handle any peaking events from the dairy industry that shares the facility with the community.

#### 1.2 RAISING BERMS


The scope of the proposed project upgrades will also include raising the three berms of the storage cell to match the elevation of the two aeration cells. The original design of the facility incorporated lower berms around the storage cell that provided ~1.80 m of liquid storage depth. To increase storage capacity of the facility, we are proposing to raise the berms ~0.9 m to match the elevation of the berms around the aeration cells. This would then allow a Full Service Level (FSL) of ~ 2.70m of liquid depth plus 1.0 m of freeboard to the top of berms.

The objective of raising the berms around the storage cell is to be able to accommodate the wet year's spring melt waters and try to avoid any emergency discharges in spring. Historically, the cell is usually sufficient storage, but in 2017 the cells were near overtopping.

The original facility was constructed with a bentonite slurry keyway around the outside berms as the containment mechanism. With raising the berms, we propose to line the interior slopes of the added height with 0.9 m of suitable clay with hydraulic conductivity that is less than  $1x10^{-7}$  cm/s. The new liner will also be keyed into the existing keyway to form a continuous liner.





The following figure shows the construction of the raised berms and new liner integrity.



The attached geotechnical report from Trek dated January 20<sup>th</sup>, 2023, details the construction and methodology of raising the lagoon berms.

The following plan shows the extent of the berms to be raised.







#### 1.3 OPERATIONAL PARAMETERS OF THE UPGRADES LAGOON

This NOA is proposing to alter the following clauses in EAL 1666 S3 "General Requirements"

#### Original Requirements:

- 2. The Licencee shall operate and maintain the aerated wastewater treatment lagoon in such a manner that:
  - (a) a minimum of 3 milligrams of dissolved oxygen per litre is detectable at all times in the top 2.5 metres of the liquid in the aerated cells.
  - (b) the organic loading on the wastewater treatment lagoon, in terms of the 5-day biochemical oxygen demand, is not in excess of 355 kilograms per day.
  - (c) the depth of the liquid in the aeration cells does not exceed 2.75 m.
  - (d) the depth of the liquid in the storage cell does not exceed 1.8 m.

#### **Proposed Alterations:**

- 2. The Licencee shall operate and maintain the aerated wastewater treatment lagoon in such a manner that:
  - (a) a minimum of 2.0 milligrams of dissolved oxygen per litre is detectable at all times in the top 2.5 metres of the liquid in the aerated cells.
  - (b) the organic loading on the wastewater treatment lagoon, in terms of the 5-day biochemical oxygen demand, is not in excess of 355 kilograms per day.
  - (c) the depth of the liquid in the aeration cells does not exceed 2.75 m.
  - (d) the depth of the liquid in the storage cell does not exceed 2.70 m.

Salinity Requirements from EAL 1666 S3 Clause 15. And 16.:

The original 1996 Licence was written when the Village of St. Claude was on its own water system and many residents were utilizing their own water softeners due to the source water hardness. As a result of the softeners which exchanges water hardness for sodium chloride ions, the wastewater stream had elevated sodium and chloride levels. As a means to address the "salinity reduction program' the community converted their drinking water source to the Pembina Valley Water Cooperative Stephenfield Regional Water Treatment Plant. This new softened water source eliminated the use of water softeners and lowered the sodium and chloride levels in the wastewater. The typical sodium levels in the PVWC supply are 25-30 mg/L (lower than the 200 mg/L objective in Clause 15), and the typical chloride levels in the supply is 20-25 mg/L.

It is therefore requested that these clauses 15 and 16 as they relate to sodium levels be removed from future Licence requirements.





#### 2 INDUSTRY FLOWS AND LOADING

The RM of Grey continues to work with the local dairy industry on their wastewater flows and is in the process of developing an Industrial Services Agreement with them. It is estimated that the process will take up to a year to finalize this agreement. Therefore, it is unknown at this time what changes will be made, if any, to the industry's loading to the lagoon. At this time, it is not anticipated that the loadings will get higher, but they could be reduced if the industry implements on-site treatment strategies.

For the purpose of design of the RM's lagoon upgrades, it is assumed that the industry loads will remain status quo and continue as they are now. This amounts to allocating a relatively high strength wastewater BOD load as noted in the table in Section 1.1.

The RM is planning for Phase 2 upgrades of their facility in the next year or two for phosphorus removal. But the design and sizing of the phosphorus treatment system cannot be finalized until the RM has a finalized ISA and a firm effluent expectation for phosphorus from the industry. It is unknown if the industry will implement on-site treatment to improve their effluent quality or contribute to a larger RM facility.

#### 3 ENVIRONMENTAL EFFECTS OF THE WORKS

As this NoA is being submitted in conjunction with the "Rural Municipality Of Grey - St. Claude Environment Act Proposal for Land Application of Lagoon Biosolids" prepared by Dillon Consulting September 2021. For conciseness, this NoA will not duplicate the general site descriptions provided in that EAP document, please refer to "Section 3.0 Description of Existing Environment in Study Area" from that EAP for the general site descriptions.

This NoA will focus on the environmental effects as they directly relate to the replacement of the aeration system and the raising of the berms.

The majority of any negative environmental effects will be during the construction phase of the project. The long-term effects, however, will be more positive by providing better treatment efficiency with the new aeration and the higher berms provides more emergency storage capacity that reduces the occurrences of emergency discharges in spring.

#### 3.1 ENVIRONMENTAL EFFECTS DURING CONSTRUCTION

#### 3.1.1 Air Quality Impacts

Construction activities with the placing of new earth along the berms will create dust and emissions from construction machinery. Dust suppression along the gravel roads used by equipment will use water sprays or mists alleviate potential dust from being raised. Air quality effects from any dust generation during construction would be localized and temporary and is considered to have a low or negligible environmental effect. Emissions from construction equipment will be temporary and minimized by having machinery operating within normal limits and outfitted with mufflers (where



May 23, 2023 Robert Boswick, P. Eng. Page 7

application) to reduce air emissions. Contributions from construction activities and operations to greenhouse gas emissions are not expected to be significantly above background levels and are unlikely to contribute significantly to overall greenhouse gas inventories from the area.

#### 3.1.2 Soils Impacts

A risk exists, during the construction of the facility, for a spill to occur from construction machinery and vehicle equipment. To reduce this risk storage of fuel, other petroleum products and lubricants will not be permitted within the area of any nearby water supply. Therefore, the risk of occurrence is small based and additionally standard construction best practices for managing clean-up and removal of any impacted soils will be used to prevent any impacts.

#### 3.1.3 Surface Water and Fish Habitat

Potential environmental impacts to surface water and fish habitat are expected to be negligible and short-term during construction. The majority of the work will take place at least 1500m from the nearest water body (Lac a Parker). Standard construction best management practices for sedimentation and erosion control will be implemented during construction to reduce potential effects to downstream aquatic life along the ditches and drains.

#### 3.1.4 Climate Change Adaptation

As previously mentioned, contributions from construction activities and operations to greenhouse gas emissions are not expected to be significantly above background levels and are unlikely to contribute significantly to overall greenhouse gas inventories from the area.

#### 3.2 ENVIRONMENTAL MITIGATION DURING CONSTRUCTION

#### 3.2.1 Air Quality

Well maintained vehicles and equipment and reduction of unnecessarily transportation and idling of vehicles will assist in mitigating air quality impacts.

The control of dust with water sprays or an approved dust suppressant will limit the impact of dust to the air quality. Prompt re-establishment of vegetation disturbed during construction and also limiting certain work to periods of low winds will also help mitigate air quality impacts.

#### 3.2.2 Soils

Preparation of an emergency response plan to mitigate potential impacts to soil by contaminants from petroleum products as well as use and availability of on-site spill clean-up equipment and materials, using properly maintained equipment and fuelling procedures.

Minimal ground disturbance of areas not previously disturbed is anticipated during the construction phase. The reestablishment of vegetation and backfill of any short trenches or excavations will occur as soon as possible after any disturbance to reduce the loss of soil due to wind or water erosion.



May 23, 2023 Robert Boswick, P. Eng. Page 8

#### 3.2.3 Surface Water

Surface water issues may be mitigated during construction by redirecting surface run-off, pumping accumulated water to adjacent ditches and installing proper erosion control practices such as silt fences and erosion control blankets.

Properly maintained, operated and fueled equipment will assist with the mitigation of potential fuel or petroleum spills. Manitoba Sustainable Development will be notified through the emergency response line and appropriate measures will be taken according to Manitoba Sustainable Development requirements.

Washing, refueling and servicing machinery and storage of fuel and other materials for the machinery will occur in such a way to prevent any deleterious substances from entering the water. Vehicles will stay on established roads and not unnecessarily disturb riparian zones. Any disturbed vegetation will be re-established as soon as possible.

#### 3.2.4 Groundwater

The same mitigation efforts as described for surface water can be applied to as mitigation measures to reduce potential impact to any groundwater.

#### 3.2.5 Vegetation and Wildlife

The establishment of vegetation will occur as soon as practically possible for disturbed areas. Minimizing laydown areas and construction activities will act as a measure to reduce disturbance to soils, and vegetation. Proper noise control and dust control as previously discussed will be implemented to mitigate potential impacts.

#### 3.2.6 Fisheries

Fisheries impacts will be mitigated by controlling run-off and any construction related discharge to the watercourse to reduce potential harmful effects. The work area will be set back from riparian zones and a vegetated buffer will remain intact to minimize any sediment from entering drainage channels. Proper erosion and sedimentation control measures for working near water will be implemented. These measures will limit any short-term temporary impact to fisheries during construction activities.

#### 3.2.7 Noise and Vibration

Unnecessary operation of equipment, properly muffled vehicles and equipment on site and properly maintained equipment will be assist in mitigating noise and vibration issues.





#### 3.3 ENVIRONMENTAL EFFECTS FROM OPERATING THE UPGRADED FACILITY

#### 3.3.1 Air Quality Odour Considerations

It is anticipated that during the operation of the upgraded facility there would not be any release of pollutants to the air. It is not anticipated that the operation of the upgraded facility will create any more odours than the current facility, the improved aeration may reduce odours with the more effective aeration equipment.

#### 3.3.2 Soils Impacts

The raised berms will maintain containment around the storage cell with a clay liner to current standards. Potential adverse impacts to soil quality are assessed to be negligible.

#### 3.3.3 Groundwater Impacts

The proposed activities associated with the upgrades are not expected to impact groundwater resources. The storage cell will be lined with compacted clay liner. The potential environmental effects to groundwater resources are therefore expected to be negligible during operations.

#### 3.3.4 Wildlife Habitat

The potential effects to wildlife and habitat loss were assessed to be negligible as all activities are occurring in areas previously disturbed.

#### 3.3.5 Surface Water and Fish Habitat

The proposed new facility is expected to result in improved wastewater effluent over the current 40-year-old equipment. The expected reduction in BOD, Fecal and ammonia loading in the effluent should have a positive effect on the receiving surface water quality.

The potential for increased hydraulic retention in the storage pond should also result in effluent temperatures that are close to the receiving body ambient temperature. This should minimize any temperature shock, or effects in any receiving streams.

#### 4 SCHEDULE OF CONSTRUCTION

The RM has \$2.0M in funding with the Manitoba Water Services Board (MWSB) for the entire phase of this project (which includes biosolids removal). The Project will be managed by the MWSB.

The proposed schedule of construction and biosolids removal will likely revolve around the land application timeline. Time is of the essence given the failure rate of the existing aeration system.

At this time, we are anticipating the preferred land application time is in late fall 2023 when the crop is taken off but tendering of the project will also not occur until the EAP and NoA are approved.



May 23, 2023 Robert Boswick, P. Eng. Page 10

Based on these timelines, the following is our best estimation of the construction schedule:

- Construct new blower building in summer/fall of 2023.
- 2. Set up pumps and piping for biosolids removal in summer of 2023
- 3. Raise berms around storage cell August/September 2023 (completion in spring 2024 if time runs out).
- 4. Install new blowers and new aeration header in fall/winter 2023/24.
- 5. Remove biosolids for land application from storage cell and aerated cells in fall of 2023 (assume 3-4 weeks for application process)
- 6. Test storage cell to see if BOD is high in prior to fall discharge. Consider pumped re-circulation loop back to aerated cells if BOD is too high for any discharge.
  - Stirring up the cells may increase BOD and Fecal levels. Chlorination may be required if levels are still too high.
- 7. Remove aeration from Cell #1 and replace after biosolids are removed late 2023.
- 8. Remove aeration from Cell #2 and replace after biosolids are removed late 2023.
- 9. Test storage cell to see if BOD is high after aeration replacement works. Consider pumped recirc loop back to aerated cells if BOD is too high for any discharge.
- Once all aeration equipment is commissioned in later 2023, the system would be cut over to new equipment and the old equipment would be decommissioned and removed in early 2024.



#### HNICAL Quality Engineering | Valued Relationships

January 20, 2023 Our File No. 0115-079-00

Mr. Ken Anderson, P. Eng. Manager, Water Associated Engineering (Sask.) Ltd. 203 - Number Five Donald Street, Winnipeg, MB R3L 2T4

RE: St. Claude Wasterwater Lagoon Aeration Upgrades
Permeability Assessment of a Potential Borrow Source

As requested by Associated Engineering Ltd. (Associated), TREK Geotechnical Inc. (TREK) has completed a permeability assessment of material from a potential borrow source. The location of the borrow source was not provided, but was from the same source used for the Elm Creek Landfill project. This material is to be used to construct a new clay liner that satisfies the provincial requirements for low permeability barrier to have a hydraulic conductivity less than  $1 \times 10^{-9}$  m/s ( $1 \times 10^{-7}$  cm/s). A bulk sample was delivered to TREK on December 7, 2022. TREK's scope of work includes laboratory testing, interpretation of results and recommendations for the new compacted clay liner.

#### **Laboratory Testing**

Laboratory testing was performed to classify the soil and determine the permeability characteristics of the material. The specific tests undertaken include Atterberg Limits, grain size analysis (hydrometer method) and a hydraulic conductivity test using a flexible wall permeameter. Table 01 summarizes the laboratory tests performed; a full summary of detailed test results are attached.

Atterberg Grain-Size Hydraulic Soil Distribution (%) limits Source Location Conductivity Description PL LL Sand Silt Clay (m/s) Borrow High Plastic for Elm 2.33×10<sup>-10</sup> unknown 24 75 51 1.8 26.8 71.4 Creek Clay Landfill

**Table I: Soil Permeability Properties** 

The material is a high plastic clay well suited for use as a low permeability barrier. In general, a liquid limit (LL) greater than 50 along with a clay content greater then 30% suggests the hydraulic conductivity of the material will likely be less 1 x 10<sup>-9</sup> m/s (1 x 10<sup>-7</sup> cm/s). This is supported by the hydraulic conductivity test conducted on a reconstituted sample, as shown above in Table 1. Typically, a clay liner is compacted to 95% of the Standard Proctor Maximum Dry Density (SPMDD) at or near the optimum moisture content. In this regard, the clay borrow sample was compacted (reconstituted) to approximately 95% of the SPMDD at optimum moisture and then a sample suitable for the flexible wall test apparatus was extracted from the Proctor mold. The hydraulic conductivity of the reconstituted sample meets the provincial permeability requirement.

#### **Clay Liner Recommendations**

TREK has reviewed the attached construction drawing related to the new clay liner and has no comments in terms of the liner layout and geometry. The following recommendations apply to design and construction of the clay dike:

- 1. The fill for the new compacted clay liner should be highly plastic with a liquid limit greater than 50% and a clay content greater then 30%.
- 2. The clay fill for the liner and the new common fill material should be well mixed and homogeneous. The fills are to be unfrozen, free from organic matter, debris and deleterious materials.
- 3. Topsoil and compressible, or otherwise unsuitable materials, should be stripped and removed from the sub-grade prior to dike construction.
- 4. Excavation should be completed in a manner that minimizes disturbance to the existing clay cap.
- 5. Top of the existing common embankment after excavation should be scarified prior to placement of the new clay liner or the new common fill when slopes are 6H:1V. For excavated slopes sitting at 4H:1V or steeper, placement of new material (clay liner or common fill) on top of the existing common embankment should be benched at the interface of the two materials.
- 6. The existing clay cap and the existing common embankment material should be protected from mechanical disturbance, freezing, drying, or inundation with water at all times. If any of these conditions occur these materials should be scarified, moisture conditioned as appropriate, and recompacted to a minimum of 95% of the SPMDD or the disturbed zone may have to be excavated and replaced clay fill.
- 7. The clay fill and new common fill embankment should be placed in a direction parallel to the dike axis in level, uniform lifts, no thicker than 150 mm and compacted to a minimum of 95% of the SPMDD and be within 2% of the optimum moisture content. If the new common fill material is non-cohesive (e.g. sands, gravels), the compaction target is a minimum of 98% of the SPMDD.

The sample provided is suitable for the new compacted clay liner as it meets the provincial requirements and recommendations listed above. The liquidity index of the material indicates it is workable and can be compacted by traditional compaction equipment intended for clay soils provided the in-situ moisture content does not notable change.

It is our understanding that the intent is to leave as much as possible of the existing clay cap in place. In this regard, TREK will assess the condition of the existing clay cap during construction to determine if part or all the existing clay cap is suitable and can be left in place. Additional testing may be undertaken at that time to confirm the suitability of the existing clay cap.

#### Closure

The information provided in this report is in accordance with current engineering/testing principles and practices (Standard of Practice). The findings of this report were based on information and materials provided. Natural soil deposits inherently can be variable. If materials proposed to be utilized are different than those presented here, we should be notified to adjust our findings if necessary.

All information provided in this letter is subject to our standard terms and conditions for engineering services, a copy of which is provided to each of our clients with the original scope of work or standard engineering services agreement. If these conditions are not attached, and you are not already in possession of such terms


and conditions, contact our office and you will be promptly provided with a copy.

This letter has been prepared by TREK Geotechnical Inc. (the Consultant) for the exclusive use of Associated Engineering Ltd. (the Client) and their agents for the work product presented in the letter. Any findings or recommendations provided in this letter are not to be used or relied upon by any third parties, except as agreed to in writing by the Client and Consultant prior to use.

If you have any questions, please contact the undersigned.

Kind Regards,

#### TREK Geotechnical



Nelson John Ferreira, P.Eng. Senior Geotechnical Engineer





Brent Hay, M.Sc., P.Eng. Senior Geotechnical Engineer











AE PROJECT No. SCALE APPROVED DATE REV DESCRIPTION 2019<del>-</del>4231 NTS

2023-01-11 0 ISSUED FOR NOA FIGURE 1

MANITOBA WATER SERVICES BOARD RM OF GREY

CIVIL ST. CLAUDE LAGOON UPGRADES BERM AND LINER UPGRADES



#### **INICAL** Quality Engineering | Valued Relationships

January 11, 2023 Our File No. 1000-078-10

Ken Anderson, P.Eng., Associated Engineering (Sask.) Ltd. 203 – Number Five Donald Street Winnipeg, Manitoba. R3L 2T4

#### RE Laboratory Testing Results for St. Claude Lagoon – Hydraulic Conductivity

Please see the attached Hydraulic Conductivity report. A sample of clay material was brought to TREK on December 7, 2022. This report contains Atterberg Limits, grain size analysis (Hydrometer method), Standard proctor and the hydraulic conductivity test results for sample L22-676 using a flexible wall permeameter following ASTM D5080-16. The sample was remolded to 95.3% of SPMDD.

The test report for the sample is attached showing the calculated hydraulic conductivity values corrected to  $20^{\circ}$ C are as follows:

Sample L22-676 2.35E-10 m/s ( 2.35 x 10<sup>-8</sup> cm/s)

The services undertaken by TREK on this assignment constitutes testing services only and engineering evaluation or interpretation has not been undertaken, but is available upon request

If you have any questions or require additional information or clarifications, please contact Angela at 204.792.8458.

Kind Regards,

TREK Geotechnical

Review Control:

Treparea by. ATK Reviewea by. ATK Checkea by. Not		Reviewed By: AFK	Checked By: NJF
---	--	------------------	-----------------

www.trekgeotechnical.ca 1712 St. James Street Winnipeg, MB R3H 0L3

Tel: 204.975.9433 Fax: 204.975.9435

## **Atterberg Limits ASTM D4318-10e1**

Project No. 1000-078-10 Client Associated Engineering Project St. Claude Lagoon

Source Elm Creek Landfill L22-676 Sample #


Depth (m) N/A Sample Date 07-Dec-22 06-Jan-22 **Test Date** Technician AD



**Liquid Limit** 75 **Plastic Limit** 24 **Plasticity Index** 51

#### Liquid Limit

Liquid Littiit				
Trial #	1	2	3	
Number of Blows (N)	17	21	33	
Mass Tare (g)	13.844	14.046	13.874	
Mass Wet Soil + Tare (g)	23.937	24.065	23.022	
Mass Dry Soil + Tare (g)	19.528	19.755	19.157	
Mass Water (g)	4.409	4.310	3.865	
Mass Dry Soil (g)	5.684	5.709	5.283	
Moisture Content (%)	77.569	75.495	73.159	



#### **Plastic Limit**

Trial #	1	2	3	4	5
Mass Tare (g)	14.209	13.883			
Mass Wet Soil + Tare (g)	21.167	20.095			
Mass Dry Soil + Tare (g)	19.817	18.908			
Mass Water (g)	1.350	1.187			
Mass Dry Soil (g)	5.608	5.025			
Moisture Content (%)	24.073	23.622			

Note: Additional information recorded/measured for this test is available upon request.



Project No. 1000-078-10

Client Associated Engineering
Project St. Claude Lagoon

Source Elm Creek Landfill

 Sample #
 L22-676

 Depth (m)
 N/A


 Sample Date
 7-Dec-22

 Test Date
 9-Jan-23

 Technician
 JC



Gravel	0.0%
Sand	1.8%
Silt	26.8%
Clay	71.4%



Gravel		Sa	and	Silt and Clay	
Particle Size (mm)	Percent Passing	Particle Size (mm)	Percent Passing	Particle Size (mm)	Percent Passing
50.0	100.00	4.75	100.00	0.0750	98.20
37.5	100.00	2.00	99.98	0.0535	94.20
25.0	100.00	0.850	99.98	0.0380	93.57
19.0	100.00	0.425	99.96	0.0270	92.01
12.5	100.00	0.180	99.62	0.0172	91.07
9.50	100.00	0.150	99.48	0.0136	90.45
4.75	100.00	0.075	98.20	0.0100	88.88
	6- 2-			0.0072	86.38
				0.0051	84.87
				0.0037	81.74
		, c		0.0026	75.53
				0.0019	70.80
				0.0011	62.80



Project No. 1000-078-10

Client Associated Engineering
Project St. Claude Lagoon

Sample # L22-676-01


Source Elm Creek Landfill

Material Clay Sample Date N/A

 Test Date
 10-Dec-22
 Maximum Dry Density (kg/m3)
 1408

 Technician
 DS
 Optimum Moisture (%)
 28.3

Trial Number	1	2	3	4	
Wet Density (kg/m <sup>3</sup> )	1728	1778	1811	1819	
Dry Density (kg/m <sup>3</sup> )	1378	1403	1404	1393	
Moisture Content (%)	25.3	26.7	29.0	30.6	



Whitestory Higher Colleges

Note: Additional information recorded/measured for this test is available upon request.



Project No. 1000-078-10 Source Elm Creek Landfill

Associated Engineering Ltd. L22-676 Client Trek Sample # St. Claude Lagoon N/A Project Depth (m) Sample Date

N/A

**Test Date** December 14, 2022 to January 4, 2023

Angela Fidler-Kliewer Technician

#### Specimen Details


Visual Clay, silty, trace gravel (<5mm diam.), grey, moist, stiff, high plasticity

Classification

The specific gravity of the soil was assumed to be 2.65. Sample was remolded to 95.3% of SPMDD. Comments

Index Testing	29	Test Details	
Liquid Limit	75	Permeant	Distilled, de-aired water
Plastic Limit	24	Method	Constant Rate
Plasticity Index	51	Cell Pressure	126.6 kPa
Clay Content (%)	71	Influent Pressure	91.8 kPa
		Effluent Pressure	84.6 kPa
		Gradient	7 38

#### Permeation Graph



#### Elapsed Time (Days)

#### Steady Flow Permeation Data

Time Increment	Elapsed Time	Flov	v (Q)	Inflow / Outflow	Average Flow	Temperature	Corrected Hydraulic
(Days)	(Days)	Influent (mL)	Effluent (mL)	Ratio	(mL)	Correction	Conductivity, k <sub>20</sub> (m/s)
1.08	10.21	13.62	10.32	1.03	1.18	1.01	2.97E-10
1.01	11.22	14.52	11.18	1.05	0.88	1.00	2.38E-10
1.00	12.21	15.42	11.92	1.22	0.82	1.00	2.31E-10
1.02	13.23	16.10	12.53	1.11	0.65	0.99	1.73E-10

Average Temperature Corrected Hydraulic 2.35E-10 (2.35x10<sup>-8</sup> cm/s) Conductivity, k<sub>20</sub> (m/s)

Consolidation Data

	Average Height (m)	Average Diameter (m)	Moisture Content (%)	Dry Density (kN/m³)	Degree of Saturation (%)	Cell Pressure	Back Pressure
Initial	0.0987	0.0736	29.7	13.2	80.8	120.0	85.2
Final	0.1007	0.0747	40.3	12.4	98.1	120.0	84.4



			DRAWING INDEX	Κ
SHEET	DRAWING NAME	REVISION	DRAWING TITLE	DRAWING DESCRIPTION
GENERAL			1 1 1 1	
1	4231-00-g-001	0	COVER PAGE	
CIVIL				11.10
2	4231-00-c-101	0	LAGOON SITE PLAN	EXISTING
3	4231-00-c-102	0	LAGOON SITE PLAN	PROPOSED
4	4231-00-c-103	0	LAGOON CELL #1 AND #2 PLAN	AERATION REPLACEMENT
5	4231-00-c-104	0	LAGOON CELL #3 PLAN	BERM UPGRADE
6	4231-00-c-105	0	BLOWER BUILDING SITE PLAN	
7	4231-00-c-501	0	DETAILS	
BUILDING	W THE WATER AND		10000	
8	4231-00-a-101	0	MAIN FLOOR PLAN	
9	4231-00-a-102	0	ROOF PLAN	
10	4231-00-a-201	0	ELEVATIONS	EAST AND NORTH
11	4231-00-a-202	0	ELEVATIONS	WEST AND SOUTH
12	4231-00-a-501	0	DETAILS	200 - 200 -
13	4231-00-a-601	0	CODE OVERVIEW	AND SCHEDULES
STRUCTUR	AL			
14	4231-00-s-101	0	MAIN FLOOR PLAN	
15	4231-00-s-501	0	DETAILS	
PROCESS	ALCOHOLOGICA COL	200.0		
16	4231-00-d-101	0	MAIN FLOOR PLAN	BLOWER PIPING
17	4231-00-d-301	0	SECTION	10 30 0 0 0 0 0 1 km 30 0 0
MECHANICA	AL .	1300	ABBU-SYSTEM	
18	4231-00-m-001	0		
19	4231-00-m-101	0	MAIN FLOOR PLAN	HVAC AND DRAINAGE
20	4231-00-m-501	0	DETAILS	
21	4231-00-m-601	0	SCHEDULES	
ELECTRICA	L	0.711		
22	4231-00-e-001	0		
23	4231-00-e-002	0	SINGLE LINE DRAWING	
24	4231-00-e-101	0	SITE PLAN	AERATION BUILDING
25	4231-00-e-102	0	MAIN FLOOR PLAN	LIGHTING, POWER AND INSTRUMENTS
26	4231-00-e-301	0	93000000 7 TO 2 WAY VIII.W	177 - 3271 - 11
27	4231_DD_E_8D1	0	DETAILS	SINGLE LINE DIAGRAM





# **RURAL MUNICIPALITY OF GREY**

ST. CLAUDE WASTEWATER LAGOON AERATION UPGRADES M.W.S.B. #: 1493

**Issued for Tender and Construction - May 2021** 







The Manitoba Water



M.W.S.B.#: 1493 20194231-00



- 1. ALL MATERIALS AND INSTALLATION PRACTICES SHALL CONFORM TO M.W.S.B. STANDARD CONSTRUCTION SPECIFICATIONS.
  2. DECIMAL IZED NUMBERS INDICATE METERS AND WHOLE NUMBERS INDICATE MILLIMETERS.
  3. LOCATION OF UNDERGROUND SERVICES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE, BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING SERVICES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT.
  4. CONTRACTOR MUST CONFIRM WITH THE INDIVIDUAL UTILITIES FOR EXISTENCE AND EXACT LOCATIONS OF ALL THE SERVICES PRIOR TO CONSTRUCTION.
  5. CONTRACTOR MUST EXPOSE EXISTING INFRASTRUCTURE AT THE PROPOSED TIE-IN LOCATIONS TO ALLOW SITE ENGINEER TO VERIEN SIZE MATERIAL AND INVESTS PRIOR TO CONSTRUCTION OF TIE-INS.
- CONTRACTOR MUST EXPOSE EXISTING INFRASTRUCTURE AT THE PROPOSED TIE-IN LOCATIONS TO ALLOW SITE ENGINEER TO VERIFY SIZE, MATERIAL AND INVERTS PRIOR TO CONSTRUCTION OF TIE-INS.

  ALL STEL AYDOWN AREAS SHALL BE AS NOTED IN THE SPECIFICATIONS AND APPROVED BY THE OWNER AND ENGINEER.

  ALL AREAS SUBJECT TO CONSTRUCTION OPERATIONS SHALL BE RESTORED TO THE CONDITION IN WHICH THEY EXISTED PRIOR TO CONSTRUCTION. THIS INCLUDES, BUT IS NOT LIMITED TO, PAVEMENT REPAIRS, RE-GRAVELLING, TRENCH SETTLEMENT CORRECTION AND RE-SEEDING OF GRASSED AREAS, RESTORATION SHALL CONFORM TO M.W.S.B. AND MUNICIPAL STANDARDS.

  CONTRACTOR SHALL MAINTAIN THE FOLLOWING INSTALLATION DISTANCES:

  8.1. SEPARATION BETWEEN POTABLE WATER AND RAW WATER OR WASTE WATER:

  8.1.1. HORIZONTAL = 3.0 m

  8.1.2. VERTICAL = 0.46 M, POTABLE WATER ABOVE.

  8.2. MINIMUM BURY DEPTH:

  8.2.1. WITHIN CITY, TOWN AND VILLAGE LIMITS = 2.75 m

  8.2.2. RURAL AREAS = 2.4 m

  8.2.3. CROSSINGS (ROAD, DRAIN, ETC.) = 3.0 m

  8.2.4. INSTALLATIONS WITH LESS THAN MINIMUM COVER SHALL BE INSULATED AS PER M.W.S.B. SPECIFICATIONS.

  WHERE THE PROPOSED ALIGNMENT CROSSES PTH'S, PR'S, DEVELOPED ROAD ALLOWANCES, PRIVATE LANES, WATER RUNS AND WETLANDS, A TRENCHLESS METHOD OF INSTALLATION SHALL BE USED.

#### LEGEND

#### LINETYPES

COMPACTED CLAY LAYER

COMPACTED EARTH

ROAD	EXISTING	PROPOSED
CONTROL LINE		8 + + +
GRAVEL ROAD		-
EDGE OF PAVEMENT		2 3
MISCELLANEOUS		
FENCE	V	V
SILT FENCE	X	x
ABANDONED PIPE	9.	•
RAILWAY		
BOTTOM OF BANK		1 123 13 13 13 13 1
TOP OF BANK	* F (S) (A ) F F	
HEDGE	·····	
BUILDING		
WATER		
WATER MAIN		
RAW WATER	<del></del>	
POTABLE WATER	- <del></del>	<u> </u>
SANITARY SEWER		
SANITARY SEWER	<u> </u>	<u>12</u>
SANITARY FORCEMAIN	<u> </u>	12
COMMUNICATIONS / TELEP	HONE	
TELEPHONE/LINE		
UNDERGROUND TELEPHONE		5
ELECTRICAL / POWER		
POWER / COMM / CONDUIT	3	# #
OVERHEAD POWER	<u>c</u> = 4	2
UNDERGROUND POWER	G S	
GAS/OIL		
GAS		*
PROPERTY		
PARCEL / LOT LINE	200000000000000000000000000000000000000	-
EASEMENT		
ROAD ROW		-
CONCRETE	F F 5.5	
RIP-RAP / DRAIN ROCK	505050	
EARTH / NATIVE MATERIAL		
	RRRRRRRR	

### SYMBOLS

SURVEY	EXISTING	PROPOSED
IRON PIN	⊚ <i>⊭</i>	
IRON PIN (FOUND)	⊚ iFF	
MISCELLANEOUS		
TEST PIT		ТР
BORE HOLE	-0-вн	-ф-вн
RAILWAY SIGNAL LIGHT		
BOLLARD	0	•
	<u>∞</u>	OEG
SIGN	T	т.
BUSH	(0)	8
TREE (DECIDUOUS)	( )	(ن)
TREE (CONIFEROUS)	*	*
SPOT ELEVATION	EL100.000	EL 100.000
SLOPE	% 2	<u>%</u> 1
WATERMAIN		
CLEANOUT\FLUSHOUT	8	6
FIRE HYDRANT	⊕	•
MANHOLE	(W)	(10)
METER CHAMBER	(w)	₩
END CAP / PLUG	-1	-3
GATE VALVE	-b<-	-₩-
THRUST BLOCK	▶	<b>.</b>
ENCASEMENT	-	-
WATER LEVEL	$\overline{\Delta}$	
COUPLING	#	#
REDUCER	Q	٩
SANITARY SEWER		
MANHOLE	(a)	9
LIFT / PUMP STATION	LD.	æ
STORM DRAINAGE		
CULVERT INLET		$\prec^{\square}$
CULVERT OUTLET	~™	<b>→</b> □
DITCH FLOW	-	
ELECTRICAL/POWER LIGHT / LAMP STANDARD	•	<b>\$</b>
HYDRO / UTILITY POLE	-0-	-0-
GUY WIRE	$\rightarrow$	$\rightarrow$
COMMUNICATIONS / TELEF	PHONE	
	T	T





The Manitoba Water Services Board



2021MAY10 K. ANDERSON T. DYCHKO REV DATE DESIGN DRAWN

ISSUED FOR TENDER & CONSTRUCTION

DESCRIPTION

RURAL MUNICIPALITY OF GREY MANITOBA WATER SERVICES BOARD

ST. CLAUDE WASTEWATER LAGOON **AERATION UPGRADES** M.W.S.B.#: 1493 20194231-00

SCALE: AS SHOWN

NOTES AND LEGEND

DRAWING	REVISION	SHEET
4231-00-C-001	0	







Services Board

2021MAY10 K. ANDERSON T. DYCHKO REV DATE DESIGN DRAWN DESCRIPTION



RURAL MUNICIPALITY OF GREY MANITOBA WATER SERVICES BOARD

ST. CLAUDE WASTEWATER LAGOON **AERATION UPGRADES** M.W.S.B.#: 1493 20194231-00

SCALE: AS SHOWN

CIVIL LAGOON SITE PLAN

> SHEET REVISION 2 4231-00-C-101







Services Board



RURAL MUNICIPALITY OF GREY MANITOBA WATER SERVICES BOARD


ST. CLAUDE WASTEWATER LAGOON **AERATION UPGRADES** M.W.S.B.#: 1493 20194231-00

SCALE: AS SHOWN

LAGOON SITE PLAN


PROPOSED

REVISION SHEET 4231-00-C-102











ISSUED FOR TENDER & CONSTRUCTION

DESCRIPTION


RURAL MUNICIPALITY OF GREY MANITOBA WATER SERVICES BOARD


ST. CLAUDE WASTEWATER LAGOON **AERATION UPGRADES** M.W.S.B.#: 1493 20194231-00

SCALE: AS SHOWN

LAGOON CELL #1 AND #2 PLAN AERATION REPLACEMENT

DRAWING	REVISION	SHEET
4231-00-C-103	0	4







DRAWING	REVISION	SHEET
4231-00-C-105	0	6





0 2021MAY10 K. ANDERBON T. DYCHKO CONSTRUCTION

REV DATE DESIGN DRAWN DESCRIPTION




RURAL MUNICIPALITY OF GREY MANITOBA WATER SERVICES BOARD

ST. CLAUDE WASTEWATER LAGOON AERATION UPGRADES M.W.S.B.#: 1493 20194231-00

SCALE: AS SHOWN


CIVIL DETAILS

DRAWING REVISION SHEET
4231-00-C-501 0 7











2021MAY10 G. SARAZIN T. DYCHKO

REV DATE DESIGN


RURAL MUNICIPALITY OF GREY MANITOBA WATER SERVICES BOARD

ST. CLAUDE WASTEWATER LAGOON AERATION UPGRADES M.W.S.B.#: 1493 20194231-00

SCALE: AS SHOWN


BUILDING MAIN FLOOR PLAN

DRAWING	REVISION	SHEET
4231-00-A-101	0	8











ISSUED FOR TENDER & CONSTRUCTION

DESCRIPTION


RURAL MUNICIPALITY OF GREY MANITOBA WATER SERVICES BOARD

ST. CLAUDE WASTEWATER LAGOON **AERATION UPGRADES** M.W.S.B.#: 1493 20194231-00

SCALE: AS SHOWN

BUILDING ROOF PLAN

DRAWING	REVISION	SHEET
4231-00-A-102	0	9









0 2021MAY10 G. SARAZIN T. DYCHKO

REV DATE DESIGN


RURAL MUNICIPALITY OF GREY MANITOBA WATER SERVICES BOARD

ST. CLAUDE WASTEWATER LAGOON AERATION UPGRADES M.W.S.B.#: 1493 20194231-00

SCALE: AS SHOWN

BUILDING ELEVATIONS EAST AND NORTH

DRAWING	REVISION	SHEET
4231-00-A-201	0	10









1 PRE-FINISHED METAL ROOF

MATERIALS LEGEND

- 2 PRE-FINISHED METAL FACIA
- 3 PRE-FINISHED METAL SIDING
- 4 100 mm PRE-FINISHED METAL DOWNSPOUT
- 5 100 mm PRE-FINISHED METAL ROOF GUTTER

  INSULATED METAL DOOR AND FRAME
- VENTILATION EQUIPMENT (MECHANICAL)
- 8 CONTINUOUS SNOW GUARD PRE-CAST CONCRETE SPLASH PAD
- 10 SIGNAGE
- 11 LIGHTING (ELECTRICAL)
- 12 PIPING (PROCESS)



0 2021MAY10 G. SARAZIN T. DYCHKO

REV DATE DESIGN


#### RURAL MUNICIPALITY OF GREY MANITOBA WATER SERVICES BOARD

ST. CLAUDE WASTEWATER LAGOON **AERATION UPGRADES** M.W.S.B.#: 1493 20194231-00

SCALE: AS SHOWN

BUILDING **ELEVATIONS** WEST AND SOUTH

DRAWING	REVISION	SHEET
4231-00-A-202	0	11









DRAWN

2021MAY10 G. SARAZIN T. DYCHKO

REV DATE DESIGN

ISSUED FOR TENDER & CONSTRUCTION

DESCRIPTION

RURAL MUNICIPALITY OF GREY MANITOBA WATER SERVICES BOARD

ST. CLAUDE WASTEWATER LAGOON AERATION UPGRADES M.W.S.B.#: 1493 20194231-00

SCALE: AS SHOWN

BUILDING DETAILS

DRAWING	REVISION	SHEET
4231-00-A-501	0	12

MUNICIPAL ADDRESS :

TBD ST CLAUDE, MANITOBA CANADA LEGAL DESCRIPTION :

LAND USE DESIGNATION:

INDUSTRIAL

MAXIMUM HEIGHT PERMITTED:

PERMITTED: N/A ACTUAL: N/A

SITE AREA: +1,000 SQ m

REFERENCE CODE:

MANITOBA BUILDING CODE 2010 ENERGY CODE MANITOBA BUILDING CODE 2010 SECTION 9.38 MANITOBA FIRE CODE 2016

#### **BUILDING CLASSIFICATION**

CODE REVIEW

MAJOR OCCUPANCY CLASSIFICATION	GROUP F, DIVISION 3 - LOW HAZARD
SPRINKLER SYSTEM	NOT REQUIRED
BUILDING FOOTPRINT	60 SQ m (645 SQ FT)
NUMBER OF STOREYS	ONE
BUILDING AREAS	80 SQ m (845 SQ FT)
CONSTRUCTION TYPE	PERMITTED: COMBUSTIBLE OR NON-COMBUSTIBLE ACTUAL: COMBUSTIBLE
FLOOR ASSEMBLY	NOT REQUIRED FOR UNOCCUPIED SERVICE BUILDING
LOAD BEARING WALLS ASSEMBLY	NOT REQUIRED FOR UNOCCUPIED SERVICE BUILDING
ROOF ASSEMBLY	NOT REQUIRED FOR UNOCCUPIED SERVICE BUILDING
FIRE ALARM SYSTEM	NOT REQUIRED
OCCUPANT LOAD	N/A
TRAVEL DISTANCE	8.0 m (26.2 FT)
	<u> </u>

#### BARRIER FREE REQUIREMENTS

DUE TO THE NATURE OF THE PROJECT, A RELAXATION WILL BE ASSUMED TO ALLOW THE BUILDING TO BE WAVED FROM THE BARRIER-FREE ACCESS

#### ENERGY CODE REVIEW

ENERGY CODE REVIEW		
PRESCRIPTIVE PATH/TRADE OFF	NBCC 2010 9.36	
HEATING DEGREE DAY (HDD) AND ZONE	5400 7A	
WALL AREA	142 m <sup>2</sup>	
DOOR/LOUVER AREA	8.9 m <sup>2</sup>	
FENESTRATION AREA	0 m²	

#### MATERIALS SCHEDULE

COLOURED HARDENER HPT1 (GENERAL) FIBERGLASS REINFORCED PLASTIC FRP1 (REFER TO SPEC) MANUFACTURER: SEE SPEC
CLASS: SEE SPEC
COLOUR: BRIGHT WHITE
FINISH: PEBBLE, SEE SPEC FOR MANUFACTURER: SIKA TYPE: DIAMAG 7 COLOUR NAME: NATURAL CONCRETE GRAY
TYPE: FLORSEAL WB 18
COLOUR NAME: WATER CLEAR INSTALLATION INSTRUCTIONS

> PT1 (TRIM & DOOR PAINT) MANUFACTURER: DULUX
> COLOUR NAME: OWNER SELECTED
> COLOUR NUMBER: OWNER SELECTED
> FINISH TYPE: SEMI-GLOSS

#### ROOM FINISH SCHEDULE

			11001	WIT INVIOLED OF ILLDO				
TAG	ROOM	FLO	OR	WALL			CEILING	
IAG	ROOM	MATERIAL	FINISH	MATERIAL	FINISH	HEIGHT	MATERIAL	FINISH
101	BLOWER ROOM	CONCRETE	HPT1	WOOD SHEATHING	FRP1	3800	WOOD SHEATHING	FRP1

#### WALL TYPE



\* FIBRE REINFORCED PLASTIC PANEL SYSTEMS TO BE WATER TIGHT

EXTERIOR WALL 24 GA PREFINISHED METAL SIDING TYVEK AIR BARRIER 19 mm EXTERIOR GRADE PLYWOOD 38x140 STUDS @ 400 mm O/C 140 (R20) BATT INSULATION 6 MIL POLY VAPOUR BARRIER 19 mm PLYWOOD w/ LAMINATED FIBRE REINFORCED PLASTIC PANEL

W1

	1	DOOR SCHEDU	LE					
	LOCATION			DOOR	S		FRA	MES
TAG	FROM	то	SIZE	TYPE	SWING	FINISH	TYPE	FINISH
D1	BLOWER ROOM	EXTERIOR	2-915x2150	1	LH/RH	PT1	Α	PT1
D2	BLOWER ROOM	EXTERIOR	915x2150	2	RHR	PT1	Α	PT1

# DOOR TYPES FRAME TYPES DOOR TYPE 1 NARROW LITE DOOR TYPE 2 NO LITE FRAME TYPE A THERMALLY BROKEN

#### NOTES:

- ALL HARDWARE TO BE MEDIUM DUTY,
   COMMERCIAL GRADE. SEE SPECIFICATIONS.
   ALL HARDWARE TO BE KEYED TO MASTER
   KEYING SYSTEM.
   ALL CLOSERS TO HAVE 90 HOLD OPEN DEVICE.
   ALL EXTERIOR DOORS TO HAVE STOP CHAINS.
   SEE SPECIFICATION.

- 5. SEE SPECIFICATIONS.

#### ABBREVIATIONS:

ABBREVIATIONS:
INSUL = INSULATED
PS = PRESSED STEEL
PREF = PREFINISHED
MANUF = MANUFACTURER
FRR = FIRE RESISTANCE RATING
PT = PAINT

SCALE: AS SHOWN

**AERATION UPGRADES** M.W.S.B.#: 1493 20194231-00

2021MAY10 G. SARAZIN T. DYCHKO

DRAWN

RURAL MUNICIPALITY OF GREY

MANITOBA WATER SERVICES BOARD

ST. CLAUDE WASTEWATER LAGOON

REV DATE DESIGN

BUILDING

CODE OVERVIEW AND SCHEDULES

> DRAWING REVISION SHEET 4231-00-A-601 13

ISSUED FOR TENDER & CONSTRUCTION

DESCRIPTION

BEST MANAGED COMPANIES

Associated

Services Board

Engineering

The Manitoba Water




A. COORDINATION
A.1. CHECK ALL DIMENSIONS, ELEVATIONS, AND DETAILS PRIOR TO

CONSTRUCTION OR FABRICATION.

A.2. REPORT DISCREPANCIES TO THE ENGINEER BEFORE PROCEEDING WITH THE WORK.









DRAWN

2021MAY10 G. SARAZIN T. DYCHKO

REV DATE DESIGN

ISSUED FOR TENDER & CONSTRUCTION

DESCRIPTION

**RURAL MUNICIPALITY OF GREY** MANITOBA WATER SERVICES BOARD

ST. CLAUDE WASTEWATER LAGOON **AERATION UPGRADES** M.W.S.B.#: 1493 20194231-00


SCALE: AS SHOWN


STRUCTURAL MAIN FLOOR PLAN


> DRAWING REVISION SHEET 4231-00-S-101 14

	CURB SCHEDULE								
TVDE	SIZE		RE	NFORCI	NG				
TYPE	SIZE	BAR SIZE	SPACING	QTY	NOTES				
Ç-	150 HIGH X	15M		2	TOP CONTINUOUS				
CB-1	200 WIDE	10M	150 O/C		HAIRPIN DOWELS EMBEDDED				

200 INTO SLAB








MJ COUPLINGS



COLLAR

DRAIN LINE




NOTE: CONTRACTOR TO COORDINATE LAYOUT, DIMENSIONS AND ANCHORAGE OF HOUSEKEEPING PADS FOR EACH PIECE OF EQUIPMENT.









0 2021MAY10 G. SARAZIN T. DYCHKO CONSTRUCTION
REV DATE DESIGN DRAWN DESCRIPTION



RURAL MUNICIPALITY OF GREY MANITOBA WATER SERVICES BOARD

ST. CLAUDE WASTEWATER LAGOON AERATION UPGRADES M.W.S.B.#: 1493 20194231-00

SCALE: AS SHOWN

STRUCTURAL DETAILS

DRAWING	REVISION	SHEET
4231-00-S-501	0	15





IISSUED FOR TENDER &

IISSUED FOR TENDER &

O 2021MAY10 K. ANDERSON T. DYCHKO CONSTRUCTION



REV DATE DESIGN DRAWN

RURAL MUNICIPALITY OF GREY
MANITOBA WATER SERVICES BOARD


ST. CLAUDE WASTEWATER LAGOON AERATION UPGRADES M.W.S.B.#: 1493 20194231-00

SCALE: AS SHOWN

PROCESS MAIN FLOOR PLAN BLOWER PIPING


 DRAWING
 REVISION
 SHEET

 4231-00-D-101
 0
 16












#### RURAL MUNICIPALITY OF GREY MANITOBA WATER SERVICES BOARD

ST. CLAUDE WASTEWATER LAGOON AERATION UPGRADES M.W.S.B.#: 1493 20194231-00

SCALE: AS SHOWN

PROCESS SECTION

DRAWING	REVISION	SHEET		
4231-00-D-301	0	17		



Associated Engineering





Services Board

Grey

DRAWN

DESCRIPTION

2021FEB08 K. ANDERSON T. DYCHKO

DESIGN

RURAL MUNICIPALITY OF GREY MANITOBA WATER SERVICES BOARD

ST. CLAUDE WASTEWATER LAGOON AERATION UPGRADES M.W.S.B.#: 1493 20194231-00

SCALE: AS SHOWN

MECHANICAL

DRAWING	REVISION	SHEET
4231-00-M-001	Α	18





103UED FOR TENDER & CONSTRUCTION CONSTRUCTION

DESCRIPTION



#### RURAL MUNICIPALITY OF GREY MANITOBA WATER SERVICES BOARD

ST. CLAUDE WASTEWATER LAGOON AERATION UPGRADES M.W.S.B.#: 1493 20194231-00


SCALE: AS SHOWN

REV DATE DESIGN

MECHANICAL MAIN FLOOR PLAN HVAC AND DRAINAGE

 DRAWING
 REVISION
 SHEET

 4231-00-M-101
 0
 19







SUPPORT HOOD TO STRUCTURE AND SEAL ALL AROUND

SILL FLASHING

FRAMING AROUND OPENING

1.6 mm GALVANIZED WEATHER HOOD




MOTORIZED DAMPER. SIZE DAMPER TO MATCH FAN OUTLET FLANGE


ANGLE SUPPORT (MOUNT FAN IN ACCORDANCE W/ MANUFACTURERS RECOMMENDATIONS)

WALL SLEEVE BETWEEN FAN & DAMPER

EXHAUST FAN













Services Board

ISSUED FOR TENDER & CONSTRUCTION 2021MAY10 K. ANDERSON T. DYCHKO REV DATE DESIGN DRAWN DESCRIPTION



RURAL MUNICIPALITY OF GREY MANITOBA WATER SERVICES BOARD

ST. CLAUDE WASTEWATER LAGOON **AERATION UPGRADES** M.W.S.B.#: 1493 20194231-00

SCALE: AS SHOWN

MECHANICAL DETAILS

> DRAWING REVISION SHEET 20 4231-00-M-501

	FAN SCHEDULE													
TAG	MANUFACTURER	MODEL	SERVICE	LOCATION	SERVICE	AIR FLOW (L/s)	ESP (Pa)	FAN RPM	ARRANGEMENT	DRIVE TYPE	BHP (W)	MOTOR POWER (W)	V/Ph/Hz	NOTES
EF-101	GREENHECK	SE1-18-429-VG	EXHAUST	BLOWER BLDG	EXHAUST	1700	65	1750	DIRECT DRIVE	VSD	435	560	120/1/60	1, 4, 5, 11, 13
CF-501	CANARM	CP36 F&R	CIRCULATION	BLOWER BLDG	CIRCULATION	1427	125	365	SUSPENDED	DIRECT	28	97	120/1/60	1

1700

1700

600X550

600X600

C/W VARIABLE SPEED CONTROLLER MOUNTED ON WALL
 C/W VARIABLE SPEED CONTROLLER MOUNTED ON HOUSING
 C/W BACKDRAFT DAMPER
 C/W NEOPRENE VIBRATION ISOLATION
 C/W ACOUSTIC LINED CABINET

SPARK RESISTANT (CLASS 1, DIV. 2)
 CW REVERSIBLE MOTOR AND CONTROL
 CW FAN CAGE
 CONNECT TO WALL TOGGLE SWITCH
 INTERLOCK WITH LIGHTS

SERVICE

INTAKE

EXHAUST

CONTROL

OPEN/CLOSE

OPEN/CLOSE

TYPE

OPPOSED

CW BIRDSCREEN
 CW ALUMINUM WALL/ROOF CAP
 CW DISCONNECT SWITCH
 CW AIR PROVING CURRENT SENSOR WITH REMOTE ALARM INTERLOCKS FOR AIR PROVING

PROVIDES COOLING. CONNECT TO THERMOSTAT
 PROVIDES COOLING AND DEHUMIDIFICATION. CONNECT TO THERMOSTAT AND HUMIDISTAT.

120/1/60

120/1/80

D	AMPER SCI	HEDULE			
BLADE ORIENTATION	FLOW AREA (mm²)	AIR FLOW RATE (L/s)	DIMENSIONS (mm x mm)	V/Ph/Hz	NOTES

1, 2

1, 2

TAMCO

MANUFACTURER

MODEL

9000-MR

9000-MR

CW BELIMO LF120 US SPRING RETURN ACTUATOR.
 C/W TAMCO 8000 INSECT SCREEN IN DUCT. SLIDE OUT SIDE.

			ELE	CTRIC UNIT I	HEATER	SCHEDULE				
TAG	MANUFACTURER	MODEL	LOCATION	INPUT/OUTPUT CAPACITY (kW)	AIR FLOW (L/s)	TEMPERATURE RISE (°C)	MOTOR RPM	MOTOR POWER (W)	V/Ph/Hz	NOTES
EUH-101	OUELLET	OAS05038AM	PUMP AREA	5.0	330	13	1550	5.0	208/3/60	1, 2, 4

LOCATION

BLOWER BLDG

CONTROLLED BY WALL MOUNTED THERMOSTAT CW ADJUSTABLE LOUVER DIFFUSER SURFACE WALL MOUNT CEILING MOUNT


TAG

MD-101

MD-102







ISSUED FOR TENDER & CONSTRUCTION 0 2021MAY10 K. ANDERSON T. DYCHKO REV DATE DESIGN DRAWN DESCRIPTION



RURAL MUNICIPALITY OF GREY MANITOBA WATER SERVICES BOARD

ST. CLAUDE WASTEWATER LAGOON **AERATION UPGRADES** M.W.S.B.#: 1493 20194231-00

SCALE: AS SHOWN

MECHANICAL SCHEDULES

> DRAWING REVISION SHEET 21 4231-00-M-601







T. DYCHKO

DRAWN

ISSUED FOR TENDER &

DESCRIPTION

RURAL MUNICIPALITY OF GREY MANITOBA WATER SERVICES BOARD

ST. CLAUDE WASTEWATER LAGOON AERATION UPGRADES M.W.S.B.#: 1493 20194231-00

SCALE: AS SHOWN

2021MAY10 8, FRIEL

DESIGN


REV DATE


ELECTRICAL

DRAWING	REVISION	SHEET
4231-00-E-001	0	22













T. DYCHKO

DRAWN

ISSUED FOR TENDER & CONSTRUCTION

DESCRIPTION

RURAL MUNICIPALITY OF GREY MANITOBA WATER SERVICES BOARD

ST. CLAUDE WASTEWATER LAGOON **AERATION UPGRADES** M.W.S.B.#: 1493 20194231-00

SCALE: AS SHOWN


2021MAY10 8. FRIEL

REV DATE DESIGN

ELECTRICAL


SINGLE LINE DRAWING

DRAWING	REVISION	SHEET		
4231-00-E-002	0	23		










LEGEND ORDINARY LOCATION: BLOWER ROOM 101

PLAN MAIN FLOOR AREA CLASSIFICATIONS



		LIG	HTING FIX	TURE SC	HEDUI	_E					
FIXTURE TAG No.		EQUI	PMENT INFOR	MATION							2000
	DESCRIPTION	MANUFACTURER & CATALOGUE No.	MOUNTING	MOUNTING	WOLTS	FIXTURE	WATTO		LAN	MPS .	REMARKS
	DESCRIPTION	MANUFACTURER & CATALOGUE No.	TYPE	HEIGHT	VOLTS	SIZE	WATTS	No.	TYPE	K-VALUE	
А	VAPOUR TIGHT LED FIXTURE	METALUX: VTLED-LD4-15-DR-UNV-L840-CD2-WL-U	SURFACE	CEIL NG	120 V	400X1320	138 W		LED	4000	CE L NG MOUNT
В	DOORLIGHT	LUMARK: XTOR6BRI -Y-CB-PC1-120V	SURFACE	2300 AFE	1201/	250X149	58 W	-1	LED	2999	PHOTOCELL

2300 AFF 120 V

2 5W MR16 LED

WALL

LUMACELL: LNC-1-BLANK-W-12N60-LD9-AT

EMERGENCY LIGHT / EXIT LIGHT COMBO



RURAL MUNICIPALITY OF GREY MANITOBA WATER SERVICES BOARD

ST. CLAUDE WASTEWATER LAGOON **AERATION UPGRADES** M.W.S.B.#: 1493 20194231-00

SCALE: AS SHOWN

0 2021MAY10 8. FRIEL


REV DATE DESIGN

**ELECTRICAL** MAIN FLOOR PLAN LIGHTING, POWER AND INSTRUMENTS

DRAWING	REVISION	SHEET
4231-00-E-102	0	25









RURAL MUNICIPALITY OF GREY MANITOBA WATER SERVICES BOARD

ISSUED FOR TENDER & CONSTRUCTION

DESCRIPTION

ST. CLAUDE WASTEWATER LAGOON AERATION UPGRADES M.W.S.B.#: 1493 20194231-00

SCALE: AS SHOWN

0 2021MAY10 S. FRIEL


REV DATE DESIGN

ELECTRICAL


DRAWING	REVISION	SHEET
4231-00-E-301	0	26

















TYPICAL DETAIL	NTS
TRENCHING	

LOCAT	TION: BLOWER ROOM	VOLTAG	E: 120/20	8V									PHASE: 3 WIRE: 4	
MOUNTING: SURFACE BUS RATING: 100A														
INCOM	MING LUGS: YES	MAIN BR	EAKER: N	10										
MANU	FACTURER:	FEEDER												
ССТ	DESCRIPTION	WATTAGE		WATTAGE		WATTAGE BKR BUS			BKR	-	WATTAGE		DESCRIPTION	ССТ
No.	51803280320050			AMPS	Α	В	ВС	AMPS	35/25/37(2)				No.	
1	ELECTRICAL HEATER (5kW)	1667			25A	Α			20A				SPARE	2
3			1667		3P		В		20A				SPARE	4
5				1667				C	30A			1600	EXHAUST FAN, MD-101 AND MD-102	6
7	RECEPTACLES	500			20A	Α			15A	100			CEILING FAN	8
9	LIGHTS		650		15A		В		15A		1200		EXTERIOR RECEPTACLES	10
11	SPARE				20A			С	20A				SPARE	12
13	SPARE				20A	Α			20A				SPARE	14
15	SPARE				20A		В		20A				SPARE	16
17	SPARE				20A		- 7	C	20A		1		SPARE	18
19	SPACE					Α					fi i		SPACE	20
21	SPACE						В						SPACE	22
23	SPACE							С					SPACE	24
25	SPACE		7			Α	-7	-2			1		SPACE	26
27	SPACE						В						SPACE	28
29	SPACE					- I		С					SPACE	30
	SUBTOTALS:	2167	2317	1687						100	1200	1600	6	
NOTE:													9E41-1-12-1-14-1-1-1-1-1-1-1-1-1-1-1-1-1-1	
	NOTES GROUND FAULT BREAKER WITH	JUMA I RIP.											PHASE A TOTAL - 22	
2. " D	ENOTES GFI BREAKER WITH 5mA TRIP.												PHASE B TOTAL - 35	
													PHASE C TOTAL - 32	87
													PANEL LOAD TOTAL - 90	51 W





DRAWN

DESCRIPTION

S BEST MANAGED COMPANIES

Associated Engineering

The Manitoba W Services Board



RURAL MUNICIPALITY OF GREY MANITOBA WATER SERVICES BOARD

ST. CLAUDE WASTEWATER LAGOON **AERATION UPGRADES** M.W.S.B.#: 1493 20194231-00

SCALE: AS SHOWN

REV DATE DESIGN

ELECTRICAL DETAILS

SINGLE LINE DIAGRAM

REVISION SHEET 27 4231-00-E-601